



BUILDING JOB SITE CARD

City of Belle Isle

ELECTRICAL PERMIT 2018-03-075

PERMIT MUST BE POSTED ON SITE

Permit Number: 2018-03-075

Issue Date: 03-29-2018

Site Address: 6609 Franconia Dr 32812

Parcel Number: 20-23-30-1618-00-030

Subdivision:

Class: Residential

Description of Work: PHOTOVOLTAIC SYSTEM, RESIDENTIAL

Issued To: SUNRUN INSTALLATION SERVICES INC.

Business Phone: 732 552-61333

Name: JOYCE, PAUL

Contractor License EC13007964

Payment Date & Method: 4 / 12 / 2018

Visa Master Card Amex Discover Check / Money Order # 4731

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

ELECTRICAL INSPECTOR DATE COMMENTS

300 Temp Pole			
310 TUG			
320 Underground			
330 Rough			
340 Footer Steel Bonding			
350 Pool Light			
360 PrePower			
370 Meter ReSet			
380 Final			

Inspection requests are to be emailed to BI scheduling@UniversalEngineering.com; a confirmation email will be sent back to you upon scheduling. Next-Day Inspection requests must be made by 4pm. Please include the following in your request: Permit #, project address, type of inspection, date of the requested inspection, a contact name & a contact phone number. AM or PM may be requested but cannot be guaranteed.

Universal Engineering Sciences - 3532 Maggie Blvd., Orlando, FL 32811 Tel 407-581-8161

* Fax 407-581-0313 * www.universalengineering.com



City of Belle Isle
 Universal Engineering Sciences 3532 Maggie Blvd., Orlando, FL 32811
 Tel 407-581-8161 * Fax 407-581-0313 * www.universalengineering.com

APPLICATION FOR ELECTRICAL PERMIT

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.



DATE OF APPLICATION: _____ **PERMIT NUMBER** 2018-03-075
 The undersigned hereby applies for a permit to make electrical installations as indicated below. PLEASE PRINT
 Project Address 6609 Franconia Dr. Belle Isle FL 32809 ~~32812~~
 Property Owner Ralph Meloon Jr. Phone 907-252-7110
 Property Owner's Mailing Address 6609 Franconia Dr. City Belle Isle
 State FL Zip Code 32812 Parcel Id Number: 20-23-30-1618-00-030
 To obtain this information, please visit <http://www.ocpafl.org/Searches/ParcelSearch.aspx>

Class of Building: Old New **Type of Building:** Residential Commercial Other
Type of Work: New Alteration Addition Repair Low Voltage New Existing

INDICATE THE QUANTITY OF ALL EQUIPMENT TO BE INSTALLED

Dishwasher _____	Exhaust Fan _____	Disposal _____	Water Heater _____
Hood Fan _____	Dryer _____	Paddle Fan _____	Outlets _____
Fixtures _____	Spa _____	Pool _____	Switches _____
Electric Signs _____	Meter Reset _____	Low Voltage _____	Stoves _____
Pumps _____	Motors _____	Air Conditioning (tons) _____	Furnace (KW) _____

Temporary Construction Pole _____ **One (1) New Meter Service** _____ Amperage/Voltage/Phase

Meter Service Upgrade from _____ to _____ = _____
 Amperage/Voltage/Phase Amperage/Voltage/Phase Difference in Size

Relocate Existing Meter Service (No Service Size Change) _____

Other: Photovoltaic System, residential

PERMIT FEE BASED ON METER SERVICE SIZE SCHEDULE \$ _____
 (IF NO METER SERVICE WORK BEING DONE, USE VALUATION OF JOB FOR PERMIT FEE)
 VALUATION OF JOB (VALUATION OF ALL MATERIALS, LABOR, AND FIXTURES INSTALLED) \$ 18,700.00

Building Official: [Signature] Date 3-27-18
 Verified Contractor's Licenses & Insurance are on file [Signature] Date 3-27-18
need doc

Permit Fee = \$ 127.-
 Review Fee = \$ 63.50
 1% BCAIB Fee = \$ 2.00 mm
 1.5% DCA Fee = \$ 2.86
TOTAL Permit = \$ 195.36

I hereby certify that the above is true and correct to the best of my knowledge.

I hereby make Application for Permit as outlined above, and if same is granted I agree to conform to all Florida Building Code Regulations and City Ordinances regulating same and in accordance with plans submitted. The issuance of this permit does not grant permission to violate any applicable Town and/or State of Florida codes and/or ordinances.

LICENSE HOLDER SIGNATURE [Signature] **LICENSE #** EC13007964
LICENSE HOLDER NAME Paul Joyce **COMPANY NAME** Sunrun Installation Services INC.
Street Address 5208 Tampa W Blvd.
City Tampa **State** FL **Zip Code** 33634 **Phone Number** 732-552-6133
Email Address Samantha.hernandez@sunrun.com

NOTE: The Building Permit Number is required if the Electrical Installation is associated with any construction or alteration where a Building Permit has been issued.

104732
127 + 63.50 = 190.50
190.50 + 2.00 + 2.86 = 195.36

Building Permit Number _____ **PAID** 4-12-2018
UWA 47731

Permit Number: _____
 Folio/Parcel ID #: _____
 Prepared by: _____

 Return to: _____

DOCH 20180218543
 04/12/2018 09:08:39 AM Page 1 of 1
 Rec Fee: \$10.00
 Phil Diamond, Comptroller
 Orange County, FL
 MB - Ret To: SUNRUN SOLAR INSTALLATION



NOTICE OF COMMENCEMENT

State of Florida, County of Orange
 The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

- Description of property** (legal description of the property, and street address if available)
 6609 Franconia Drive, Belle Isle, FL
- General description of improvement**
 Roof Mounted Solar Panel System
- Owner information or Lessee information if the Lessee contracted for the improvement**
 Name Ralph Meloon Jr
 Address 6609 Franconia Dr. Belle Isle
 Interest in Property _____
Name and address of fee simple titleholder (if different from Owner listed above)
 Name _____
 Address _____
- Contractor**
 Name Sunrun Solar Installation Telephone Number 631-994-9025
 Address 5208 Tampa West Blvd, Tampa, FL
- Surety** (if applicable, a copy of the payment bond is attached)
 Name _____ Telephone Number _____
 Address _____ Amount of Bond \$ _____
- Lender**
 Name Lynn Pal Telephone Number (916) 290-9999
 Address 8281 Sierra College Blvd, Roseville, CA, 95661
- Persons within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by §713.13(1)(a)7, Florida Statuter.**
 Name _____ Telephone Number _____
 Address _____
- In addition to himself or herself, Owner designates the following to receive a copy of the Lienor's Notice as provided in §713.13(1)(b), Florida Statutes.**
 Name _____ Telephone Number _____
 Address _____
- Expiration date of notice of commencement** (the expiration date will be 1 year from the date of recording unless a different date is specified) _____




WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.

State of Florida, County of Orange
 I hereby certify that this is a true copy of the document as reflected in the Official Records
 PHIL DIAMOND, COUNTY COMPTROLLER
 BY: Phil Diamond D.C.
 DATED: APR 12 2018

Ralph C Meloon Jr
 Signature of Owner or Lessee, or Owner's or Lessee's Authorized Officer/Director/Partner/Manager Signatory's Title/Office

The foregoing instrument was acknowledged before me this 17 day of 02 / 14 by _____
 as Ralph C Meloon Jr for _____ name of person
 Type of authority, e.g., officer, trustee, attorney in fact Name of party on behalf of whom instrument was executed

[Signature]
 Signature of Notary Public - State of Florida



Personally Known _____ OR Produced ID 02
 Type of ID Produced _____



595 Market Street
29th Floor
San Francisco, CA 94105

March 13, 2018

Contractor Affidavit

Address: 6609 Franconia Dr. Belle Isle, FL 32812

To Whom It May Concern,

I, Paul Joyce, Contractor License EC13007964, hereby authorize the following to act as my agent(s) in obtaining permits. All person(s) are able to obtain permits on all construction permits.

Samantha Hernandez

Best regards,

Paul Joyce

Paul Joyce

STATE OF FLORIDA

COUNTY OF _____

The foregoing instrument was acknowledged before me this 13 day of 03, 2018, by (name of person acknowledging).

(NOTARY SEAL)



Jennifer Funaro

Notary Signature

Jennifer Funaro

Notary Printed Name

Personally Known _____ OR Produced Identification

Type of Identification Produced License





CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
3/16/2018


THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. IF SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Arthur J. Gallagher & Co. Insurance Brokers of CA, Inc. License #0726293 1255 Battery Street #450 San Francisco CA 94111	CONTACT NAME: PHONE (A/C, No, Ext): 415-546-9300 E-MAIL ADDRESS:	FAX (A/C, No): 415-536-8499													
	<table border="1"> <thead> <tr> <th>INSURER(S) AFFORDING COVERAGE</th> <th>NAIC #</th> </tr> </thead> <tbody> <tr> <td>INSURER A : Zurich American Insurance Company</td> <td>16535</td> </tr> <tr> <td>INSURER B : Navigators Specialty Insurance Company</td> <td>36056</td> </tr> <tr> <td>INSURER C :</td> <td></td> </tr> <tr> <td>INSURER D :</td> <td></td> </tr> <tr> <td>INSURER E :</td> <td></td> </tr> <tr> <td>INSURER F :</td> <td></td> </tr> </tbody> </table>		INSURER(S) AFFORDING COVERAGE	NAIC #	INSURER A : Zurich American Insurance Company	16535	INSURER B : Navigators Specialty Insurance Company	36056	INSURER C :		INSURER D :		INSURER E :		INSURER F :
INSURER(S) AFFORDING COVERAGE	NAIC #														
INSURER A : Zurich American Insurance Company	16535														
INSURER B : Navigators Specialty Insurance Company	36056														
INSURER C :															
INSURER D :															
INSURER E :															
INSURER F :															
INSURED Sunrun Installation Services Inc. 595 Market St 29th Floor San Francisco, CA 94105	CERTIFICATE NUMBER: 2017593343 REVISION NUMBER:														

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
B	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR <input checked="" type="checkbox"/> \$50,000 Retention GEN'L AGGREGATE LIMIT APPLIES PER: <input checked="" type="checkbox"/> POLICY <input checked="" type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:			LA17CGL2303211C	10/1/2017	10/1/2018	EACH OCCURRENCE \$1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$1,000,000 MED EXP (Any one person) \$5,000 PERSONAL & ADV INJURY \$1,000,000 GENERAL AGGREGATE \$2,000,000 PRODUCTS - COMP/OP AGG \$2,000,000 Total Policy Limit \$10,000,000
A	<input checked="" type="checkbox"/> AUTOMOBILE LIABILITY <input checked="" type="checkbox"/> ANY AUTO <input type="checkbox"/> OWNED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> HIRED AUTOS ONLY <input type="checkbox"/> NON-OWNED AUTOS ONLY			BAP915542504	10/1/2017	10/1/2018	COMBINED SINGLE LIMIT (Ea accident) \$2,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
	<input type="checkbox"/> UMBRELLA LIAB <input type="checkbox"/> EXCESS LIAB OCCUR CLAIMS-MADE DED RETENTION \$						EACH OCCURRENCE \$ AGGREGATE \$ \$
A	<input checked="" type="checkbox"/> WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below			WC013696003 WC013696103	10/1/2017 10/1/2017	10/1/2018 10/1/2018	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$1,000,000 E.L. DISEASE - EA EMPLOYEE \$1,000,000 E.L. DISEASE - POLICY LIMIT \$1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)
WC013696003 - \$25,000 Deductible; WC013696103 - FL, HI, MA, NJ, NY, OR, VA, WI only. Named Insureds: Sunrun Inc., Sunrun Installation Services Inc., Sunrun South LLC, AEE Solar, Inc., Clean Energy Experts LLC, Sunrun Solar Electrical Corporation
RE: Paul Joyce, Master Electrician.

CERTIFICATE HOLDER City of Belle Isle 1600 Nela Avenue Belle Isle, FL 32809	CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE 
---	--

© 1988-2015 ACORD CORPORATION. All rights reserved.

2017 - 2018 HILLSBOROUGH COUNTY BUSINESS TAX RECEIPT

EXPIRES SEPTEMBER 30, 2018

ACCOUNT NO.
41184
NEW BUSINESS

OCC. CODE

090.008002 ELECTRICAL CONTRACTOR

15 Employees

Receipt Fee	36.00
Hazardous Waste Surcharge	0.00
Law Library Fee	0.00
EC13007964	

BUSINESS JOYCE PAUL
5208 W TAMPA BLVD
TAMPA, FL 33634

2017 - 2018

NAME SUNRUN INSTALLATION SERVICES INC
MAILING 5208 W TAMPA BLVD
ADDRESS TAMPA, FL 33634

Paid 17-0-025145
11/02/2017 36.00

BUSINESS TAX RECEIPT

HAS HEREBY PAID A PRIVILEGE TAX TO ENGAGE
IN BUSINESS, PROFESSION, OR OCCUPATION SPECIFIED HEREON

DOUG BELDEN, TAX COLLECTOR
813-635-5200
THIS BECOMES A TAX RECEIPT WHEN VALIDATED.



152 S. Broad St
Lansdale, PA 19446
(215) 361-8040

March 12, 2018

Subject: Structural Certification for Proposed Residential Solar Installation.

Job Number: 802R-449FERG; Plan Set: Rev A, Dated 3/08/18

Client: Susan FERGUSON

Address: 5449 Jobeth Dr., New Port Richey, FL 34652

Attn: To Whom It May Concern

A field observation was performed to document the existing framing of the above mentioned address. From the field observation, the existing roof structure was observed as 1 layer Composition Shingle roofing over roof plywood supported by 2x4 Truss @ 24" OC. The roof is sloped at approximately 25 degrees and has a max truss top chord span of 6' 0" between truss web members.

Design Criteria:


- 2017 Florida Building Code 6th Edition
- Basic Wind Speed Vult = 145 mph (Vasd = 113 mph), Exposure B
- Ground Snow Load = 0 psf

Our analysis is based on the information provided by Sunrun Inc. and is isolated only to the areas where the modules are intended to be placed. After review of the field observation report, the existing roof framing supporting the proposed solar panel layout has been determined to meet or exceed the requirements based on our structural capacity calculations in accordance with applicable building codes. Therefore, no structural upgrades are required.

If you have any further questions on the above for mentioned, please do not hesitate to call.

Sincerely,
Penn Fusion Engineering LLC

Andrew D. Leone, P.E.
Principal





SolarEdge Single Phase StorEdge™ Solutions for North America



STOREDGE™

SolarEdge StorEdge™ Solutions Benefits:

- **More Energy** - DC-coupled architecture stores PV power directly to the battery without AC conversion losses
- **Simple Design & Installation** - single inverter for PV, battery storage, grid-tied and backup applications
- **Enhanced Safety** - no high voltage during installation, maintenance or firefighting
- **Full Visibility** - monitor battery status, PV production, remaining backup power and self-consumption data



SolarEdge Single Phase StorEdge Inverter for North America SE7600A-US⁽¹⁾

- Single inverter for PV, grid-tied storage and backup power
- Includes the hardware required to provide automatic backup power to backed-up loads in case of grid interruption
- Includes all interfaces needed for battery connection
- UL1741 SA certified, for CPUC Rule 21 grid compliance

	Lower Power Output	Higher Power Output	
OUTPUT - AC (LOADS/GRID)			
Rated AC Power Output	7600		VA
Max AC Power Output	8350		VA
AC Output Voltage Min-Nom-Max (L-L) ⁽²⁾	211-240-264		Vac
AC Frequency Min-Nom-Max ⁽²⁾	59.3 - 60 - 60.5		Hz
Maximum Continuous Output Current @240V	32		A
GFDI	1		A
Utility Monitoring, Islanding Protection, Country Configurable Thresholds	Yes		
Charge Battery from AC (if Allowed)	Yes		
THD	<3		%
Power factor with rated power	>0.99 (configurable; 0.9 leading to 0.9 lagging)		
Typical Nighttime Power Consumption	<5		W
OUTPUT - AC (BACKUP POWER)⁽³⁾			
Rated AC Power Output	5000 ⁽⁴⁾		VA
Max AC Power Output - Surge	6600 ⁽⁴⁾		VA
AC Output Voltage Min-Nom-Max (L-L)	211-240-264		Vac
AC Output Voltage Min-Nom-Max (L-N)	105-120-132		Vac
AC Frequency Min-Nom-Max	55 - 60 - 65		Hz
Maximum Continuous Output Current @240V - Backup Mode	21		A
Max Continuous Output Current per Phase @120V	25		A
GFDI	1		A
AC Circuit Breaker	Yes		
THD	<5		%
Power factor with rated power	0.2 leading to 0.2 lagging		
Automatic switchover time	<2		sec
Typical Nighttime Power Consumption	<5		W
INPUT - DC (PV and BATTERY)			
Transformer-less, Ungrounded	Yes		
Max Input Voltage	500		Vdc
Nom DC Input Voltage	400		Vdc
Reverse-Polarity Protection	Yes		
Ground-Fault Isolation Detection	600kΩ Sensitivity		
Maximum Inverter Efficiency	98		%
CEC Weighted Efficiency	97.5		%
INPUT - DC (PV)			
Maximum DC Power (STC)	10250		W
Max Input Current ⁽⁵⁾	23		Adc
2-pole Disconnection	Yes		
INPUT - DC (BATTERY)			
Supported Battery Types	LG Chem RESU10H, Tesla Powerwall 1		
Number of Batteries per Inverter	2 ⁽⁶⁾		
Continuous Power	3300	5000	W
Peak Power	5000	7000	W
Max Input Current	8.5	17.5	Adc
2-pole Disconnection	Yes		
DC Fuses on Plus and Minus	12A (field replaceable)	25A (field replaceable)	
ADDITIONAL FEATURES			
Supported Communication Interfaces	RS485 for battery, RS485, Ethernet, ZigBee (optional)		
Battery Power Supply	Yes, 12V / 53W		
Revenue Grade Data, ANSI C12.1	Optional ⁽⁷⁾		
Integrated AC, DC and Communication Connection Unit	Yes		
AC Disconnect	Yes		
Manual Inverter Bypass Switch	Yes		
DC Voltage Rapid Shutdown (PV and Battery)	Yes, according to NEC 2014 and 2017 690.12		
Auto-transformer thermal protection	Yes		

⁽¹⁾ These specifications apply to inverters with part numbers SE7600A-US52XXXX and connection unit model number BCU-1PH-US5

⁽²⁾ For other regional settings please contact SolarEdge Support

⁽³⁾ Not designed for standalone applications and requires AC for commissioning

⁽⁴⁾ The rated AC power output is the minimum between the AC Power Output and the battery continuous peak power

⁽⁵⁾ A higher current source may be used; the inverter will limit its input current to the values stated

⁽⁶⁾ Two LG Chem batteries connection is expected to be supported in Q3. A new LG battery will be available for such systems; at least one of the batteries must be a new one

⁽⁷⁾ Revenue grade inverter P/N: SE7600A-US520NNM2



SolarEdge Auto-transformer

SEAUTO-TX-5000

SEAUTO-TX-5000		
ELECTRICAL RATINGS		
Rated Power - Continuous	5000	VA
Rated Power - Peak	7600 for 10sec	VA
Output Voltage	120/240V Split Phase	
Max Continuous Output Current per Phase @120V	25	A
Split Phase Imbalance (@Rated Power)	Yes, up to 25A difference between phases	
Thermal Protection	Yes	
INSTALLATION SPECIFICATIONS		
AC Output conduit size / AWG range	0.75" / 14-6 AWG	
Dimensions (HxWxD)	6.7 x 7.9 x 5.5 / 170 x 200 x 140	in / mm
Weight	29.7 / 13.5	lb / kg
Min - Max Operating Temperature	-13 to +140 / -25 to +60	°F / °C
Protection Rating	NEMA 3R	
Installation	Wall mounted	



SolarEdge Electricity Meter for North America

SE-MTR240-0-000-S2

For meter specifications refer to: http://www.solaredge.us/files/pdfs/products/se_electricity_meter_na.pdf



SnapNrack™
Solar Mounting Solutions



Reviewed for Code
Compliance
Universal Engineering
Sciences



LISTED
PV Mounting System
2703



SERIES 100 UL ROOF MOUNT SYSTEM

SnapNrack Residential PV Mounting Systems
Code Compliant Installation Manual

How to Configure Your System

First calculate the spans and penetration count. There is a SnapNrack span calculation table on the back of this Manual. Determine site conditions: general building height, array pitch, the wind speed, and snow load or topographical condition. Find appropriate railspan from table.

Span Table Example


Building Height	0 - 30 ft
Array Pitch	16°
2012 IBC Wind Speed	120 mph
Snow Load	8 lbs/ft ²
Topo. Cond.	None
Rail Span	104"
Rail Span on 24" spacing roof	96" (8 ft)
Do edge/corner reductions apply	Yes, shaded cell
Edge Zone Span	72" (6 ft)
Corner Zone Span	24" (2 ft)

0-30 ft. Roof Height

Table 1A: Rail Spans (in) for Roof Slopes and Tilt Angles 0° to 19° 6063 Alloy

		Wind Load														
		Vult	110	115	120	125	130	135	140	145	150	155	160	170	180	190
		q _s	15.5	16.9	18.4	20.0	21.6	23.3	25.1	26.9	28.8	30.7	32.8	37.0	41.5	46.2
		P _s	-10.7	-11.7	-12.7	-13.8	-14.9	-16.1	-17.3	-18.6	-19.9	-21.2	-22.6	-25.5	-28.6	-31.9
Ground Snow Load (psf)	0	0														
	10	8														
	20	15														
	30	23	75	75	75											
	40	31	66	66	66	66	66	66	66							
	50	39	60	60	60	60	60	60	60	60	60					
	60	46	55	55	55	55	55	55	55	55	55	55	55			
	70	54	51	51	51	51	51	51	51	51	51	51	51	51	51	
	80	62	48	48	48	48	48	48	48	48	48	48	48	48	48	48

*CS-Consult
Structural Engineer



Series 100 UL Roof Mounted System

Safety Guidance

- Always wear the proper OSHA approved safety equipment when working on a roof.
- Safety equipment should be checked annually for wear and quality.
- Always wear proper eye protection.
- When walking on the roof avoid walking on installed rails. If this is unavoidable check L-feet for fatigue before final installation.
- Appropriate fall protection gear should be used. Extreme caution should be used when near the edge of the roof.

Notes

- The UL Listing covers bonding for a load rating up to 45 psf.
- Series 100 UL has been tested with the following UL Listed modules; See Appendix on page 40.
- These systems have been evaluated for module to system bonding, only to the requirements of UL Subject 2703.
- This system has also been evaluated for a Class A System Fire Classification for a steep-sloped roof with Type 1 modules.

Arrays can also be installed in landscape mode, with the modules oriented so that their long edge runs horizontally across the roof and the rails run up the roof slope. Landscape mode is typically used in cases where the roof has been constructed with structural elements running horizontally across the roof, but can also be used on standard residential buildings for a variety of reasons including to facilitate a convenient layout. When laying out the array, be sure to leave space for the module clamps on the rails. Module mid clamps are installed between modules in a row and require 0.5 inch of space between the modules.

Adjustable end clamps require 1.5 inches of extra rail to extend past the end of the module frame. If using the Universal End Clamp, the rail is first cut flush to the module using the rail cutting tool.

When installing multiple rows of modules, a minimum spacing gap of 1/8" should be used between rows.

Submit array plans to local permitting jurisdiction and proceed with the roof layout only when all permits for the project have been granted by the authority having jurisdiction.

Transfer the array layout to the roof using a roof marking crayon to mark the inside and outside corners of the array. Locate the estimated rafter positions and mark them in the array area with a roof marking crayon.

Transfer rail and estimated attachment locations to the roof, noting that attachments will be located at intersections of rails and rafters. Layout rails such that module frame ends do not overhang mounting rails by more than 25% of total module length.

Project Information Sections

Building Height	_____
Roof Pitch	_____
Wind Speed	_____
Snow Load	_____
Topo. Cond.	_____
Max Rail Span	_____

Roof Structure Type	_____
Roof Structure Size	_____
Roof Structure Span	_____
Roof Type & Condition	_____
Stories from the Ground	_____
Roof Orientation	_____

Series 100 UL Surveying and Layout

Tips and Tricks

- Layout the entire array on the roof by drawing all of the corners of the modules on the roof with a roof marking crayon.

- Use a chalk line to help identify the rest of the roof penetrations

- When leveling rails, hand tighten the hardware to easily level and position the rails. Once rails are level, fully tighten hardware to specified torque.

Notes

- SnapNrack engineered systems should only be used with SnapNrack components and hardware. Any alternate application may void the warranty and structural calculations could become invalid.

1) Locate the rafter



2) Drill the pilot hole



3) Prep the base



4) Attach base



5) Set the flashing



6) Attach L-Foot



Series 100 UL Flashed L-Foot

Step-by-Step Instructions

1) Locate the rafter underneath the decking of the roof by looking underneath the eaves or in the attic.

2) Drill a pilot hole through the roofing material into the rafter to ensure that the lag bolt will be located into a solid portion of the rafter. If the rafter is not found then seal the pilot hole immediately with roofing sealant.

3) Apply roofing sealant to the bottom of the base and directly onto the lag bolt to ensure a water tight seal.

4) Attach the L-foot base with a 5/16" lag bolt and a minimum embedment of 2 1/2" lag shank into the rafter. Tighten Lag bolt to seat with a hand wrench.

5) Slide the flashing underneath the row of shingles, directly above the installed standard base, and then line up the hole in the flashing with the threads on the base. It may be necessary to pry up shingles with a breaker bar.

6) Attach the L-foot to the threaded portion of the base that is protruding from the flashing. Then tighten the flange bolt over the threads to 10 - 16 ft-lbs. The L-foot can be attached in any orientation.

Notes

- Alternative 90° L Foot included in UL 2703 Listing
- SnapNrack engineered systems should only be used with SnapNrack components and hardware. Any alternate application may void the warranty and structural calculations could become invalid.

Warning

- If a pilot hole is drilled and a rafter is not found, immediately seal pilot hole with roofing sealant to avoid water damage.
- Do not over tighten hardware.
- Always wear fall protection and safety gear.

Design Tools

- SnapNrack has a suite of design tools to help configure your PV installation to be an accurate and fast install. Please visit us at: www.SnapNrack.com

Series 100 UL Standoff Post

Step-by-Step Instructions

1) Remove tile and locate the rafter



2) Drill pilot hole



3) Prep the base and attach base



4) Set flashing



5) Attach post



6) Replace tile and attach standoff clamp



1) Remove roof tile where the penetration will be installed. Locate the rafter underneath the decking of the roof by locating under the eave, in the attic, or by tapping the roof surface with a hammer.

2) Drill a pilot hole through the roofing material into the rafter to ensure that the lag bolt will be located into a solid portion of the rafter. If the rafter is not found then seal the pilot hole immediately with roofing sealant.

3) Apply roofing sealant to the bottom of the base and directly onto the lag bolt to ensure a water tight seal. Attach the Standoff base with a 5/16" lag bolt and a minimum embedment of 2 1/2" lag shank into the rafter. Tighten lag bolt to seat using a hand wrench.

4) Set the flashing by sliding the flashing underneath the row of tiles directly above the installed base, with the hole in the flashing directly above the threaded portion of the base.

5) Attach the standoff shaft by sliding it through the hole in the flashing and tightening it onto the threads protruding from the base snug with channel locks.

6) Cut the tile to fit around the flashing, replace the tile, then attach the standoff clamp by first sliding the rubber rain collar over the standoff shaft then the standoff clamp with bolt, washer and channel nut.

Notes

- SnapNrack engineered systems should only be used with SnapNrack components and hardware. Any alternate application may void the warranty and structural calculations could become invalid.

Warning

- If a pilot hole is drilled and a rafter is not found, immediately seal pilot hole with roofing sealant to avoid water damage.
- Do not over tighten hardware.
- Always wear fall protection and safety gear.

Design Tools

- SnapNrack has a suite of design tools to help configure your PV installation to be an accurate and fast install. Please visit us at: www.SnapNrack.com

Structural Calculations for the Susan FERGUSON Residence PV Installation

Date: 3/12/2018
Job Address: 5449 Jobeth Dr.
New Port Richey, FL 34652

Job Number: 802R-449FERG

Scope of Work

These calculations are for the existing roof framing which supports the new PV modules as well as the attachment of the PV system to existing roof framing. All PV mounting equipment shall be designed and installed per manufacturer's approved installation specifications.

Calculation Index

Sheet Description

- 2 Structural Geometry, Live Load, Snow Load, Wind Load, Dead Load, & Roof (1) Framing Check
- 3 Roof (1) Framing Check Continued, Roof Attachment Check, Seismic Check, & Scope of Work

Engineering Calculations Summary

Code: 2017 Florida Building Code 6th Edition
ASCE 7-10
Snow Load: S = 0 psf
Live Load: LL = 20 psf
Wind: Wind Speed Ult. (V) = 145 mph Exp. = B
PV Dead Load: DPV = 3.0 psf



Sincerely,
Penn Fusion Engineering LLC
Andrew D. Leone, P.E.
Principal



Structure Geometry:

Mean Roof Height, h_n	=	24 ft
Eave Height, h_e	=	18 ft
Building Length, L	=	65 ft
Building Width, B	=	44 ft
Module Area	=	20 ft ²
Roof Pitch, θ	=	25 degrees

Snow Load:

Ground Snow Load, p_g	=	0	Fig. 7-1
-------------------------	---	---	----------

Wind Load:

Basic Wind Speed (3s-gust)	=	145 mph	Figure 26.5-1A		
Building Occupancy Category	=	2	Table 1.5-1		
Wind Importance Factor, I_w	=	1.00	Table 1.5-2		
Exposure Category	=	B	Sec 26.7.3		
Topographic Factor, K_{zt}	=	1.00	Equation 26.8-1		
Adjustment Factor, λ	=	1.00	Figure 30.5-1		
Edge Zone, a	=	4.40 ft	Figure 30.5-1		
Uplift (0.6W)					
		Zone 1 (psf)	Zone 2 (psf)	Zone 3 (psf)	
P_{net30}	=	-33.70	-55.50	-83.45	Figure 30.5-1
$P_{net} = 0.6 \times \lambda \times K_{zt} \times P_{net30}$	=	-20.22	-33.30	-50.07	Equation 30.5-1
Downward (0.6W)					
		Zone 1 (psf)	Zone 2 (psf)	Zone 3 (psf)	
P_{net30}	=	19.90	19.90	19.90	Figure 30.5-1
$P_{net} = 0.6 \times \lambda \times K_{zt} \times P_{net30}$	=	11.94	11.94	11.94	Equation 30.5-1

Dead Load:

Roof (1):		Walls - Exterior	
Roof			
Composition Shingle	3.0 psf	Stucco	10.0 psf
5/8 OSB Sheathing	2.0	2x4 Studs @ 16"	2.0
2x4 Truss @ 24" OC	1.0	Gypsum	3.0
Misc. (Ceiling, Insulation, etc.)	1.0	Misc. (Insulation, etc.)	2.0
PV System, Ppv	3.0		
Total Roof DL =	10.0 psf	Total Wall DL =	17.0 psf

Roof (1) Framing Check:

Roof Framing	=	2x4 Truss @ 24" OC
Timber Species	=	Doug Fir-Larch #2
Max Beam Span	=	6.00 ft
b	=	1.5 in
d	=	3.50 in
Moment of Inertia, I_x	=	5.36 in ⁴
Section Modulus, S_x	=	3.06 in ³
Bending Stress, F_b	=	900 psi
Elastic Modulus, E_{min}	=	580000 psi



Wood Adjustment Factors:	C_b (Wind)	C_d (Snow)	C_{ls}	C_m	C_t
	1.60	1.15	1.15	1.00	1.00
	C_L	C_F	C_{fu}	C_i	C_r
	1.00	1.50	1.00	1.00	1.15



Engineer: SVL
 Date: 3/12/2018
 Job: 802R-449FERG
 Address: 5449 Jobeth Dr.
 New Port Richey, FL 34652
 3 of 3

Roof (1) Framing Check Continued:

PV Tributary Width, W_{pv}	=	1.60 ft
PV Tributary Length, L_{pv}	=	4.0 ft
PV Tributary Area, A_t	=	6.4 ft ²
PV Dead Point Load, $P_D = P_{pv} \times A_t$	=	17 lb
Roof Distributed Load, wDL	=	13 plf

Load Case: 0.6DL + 0.6W (CD = 1.6)

Roof Zone	=	1
$P_{up} = P_{net} \times A_t + 0.6 \times P_D \times \cos(\theta)$	=	119 lb
$M_{b(wind_up)}$	=	227 lb-ft
$F_b'(wind) = F_b \times C_D \times C_{Ls} \times C_{M} \times C_t \times C_L \times C_F \times C_{Fu} \times C_i \times C_{Cr}$	=	2857 psi
Mallowable = $S_x \times F_b'(wind)$	=	729 lb-ft
	>	227
		OK

Load Case: DL + 0.6W (CD = 1.6)

$P_{down} = P_{net} \times A_t + P_D \times \cos(\theta)$	=	94 lb
$M_{b(wind_down)}$	=	263 lb-ft
$F_b'(wind) = F_b \times C_D \times C_{Ls} \times C_{M} \times C_t \times C_L \times C_F \times C_{Fu} \times C_i \times C_{Cr}$	=	2857 psi
Mallowable = $S_x \times F_b'(wind)$	=	729 lb-ft
	>	263
		OK

Rafter Attachments: 0.6D+0.6W (Zone 2)

$P_{uplift} = A_t \times P_{net}$	=	203 lb
Connector Uplift Capacity per SnapNRack Test Results	=	309 lb
5/16" Lag Screw Withdrawal Value	=	266 lb/in
Lag Screw Penetration	=	2.50 in
Allowable Capacity with Co	=	1064 lb
	>	203
		OK
	>	203
		OK

Seismic Check:

Existing Dead Load:		Solar Dead Load:	
$A_{roofexisting}$	= 2860 ft ²	W_{panel}	= 42 lb
$W_{roofexisting}$	= 20020 lb	Num_{panel}	= 31
$A_{wallexisting}$	= 3924 ft ²	W_{panel_tot}	= 1302 lb
$W_{wallexisting}$	= 66708 lb	W_{bos}	= 304 lb
W_{total}	= 86728 lb	W_{array}	= 1606 lb

$\%increase = (W_{total} + W_{array}) / W_{total} = \frac{88334}{86728} * 100\% - 100\% = 1.85\% **$

**The increase in weight as a result of the solar system is less than 10% of the existing structure and therefore no further seismic analysis is required.

Limits of Scope of Work and Liability

We have based our structural capacity determination on applicable building codes, professional engineering inspection and design experience, opinions and judgments. The calculations produced for this dwelling's assessment are only for the proposed solar panel installation referenced in the stamped plan set and were made according to generally recognized structural analysis standards and procedures.





Reviewed for Code
Compliance
Universal Engineering
Sciences

SOLAR'S MOST TRUSTED



REC TWINPEAK 2 SERIES

**PREMIUM SOLAR PANELS
100% MADE IN SINGAPORE**

REC TwinPeak 2 Series solar panels feature an innovative design with high panel efficiency and power output, enabling customers to get the most out of the space used for the installation.

Combined with industry-leading product quality and the reliability of a strong and established European brand, REC TwinPeak 2 panels are ideal for residential and commercial rooftops worldwide.

INTEGRATED MANUFACTURING IN SINGAPORE



WAFERS



CELLS



MODULES

























SCOPE OF WORK

- **SYSTEM SIZE:** 9405W DC, 10000W AC
- **MODULES:** (33) REC SOLAR: REC285TP2 BLK
- **INVERTER(S):**
(1) SOLAREEDGE TECHNOLOGIES: SE10000A-US WITH REVENUE GRADE METERING
- **RACKING:** SNAPRACK SERIES 100 UL; FLASHED L FOOT. SEE PEN D03.

GENERAL NOTES

- ALL WORK SHALL COMPLY WITH NEC 2014, 2017 FBC 6TH EDITION, MUNICIPAL CODE, AND ALL MANUFACTURERS' LISTINGS AND INSTALLATION INSTRUCTIONS
- PHOTOVOLTAIC SYSTEM WILL COMPLY WITH NEC 2014.
- ELECTRICAL SYSTEM GROUNDING WILL COMPLY WITH NEC 2014.
- PHOTOVOLTAIC SYSTEM IS UNGROUNDED. NO CONDUCTORS ARE SOLIDLY GROUNDED IN THE INVERTER. SYSTEM COMPLIES WITH 690.35.
- MODULES CONFORM TO AND ARE LISTED UNDER UL 1703
- INVERTER CONFORMS TO AND IS LISTED UNDER UL 1741.
- RACKING CONFORMS TO AND IS LISTED UNDER UL 2703.
- SNAPRACK RACKING SYSTEMS, IN COMBINATION WITH TYPE I, OR TYPE II MODULES, ARE CLASS A FIRE RATED.
- RAPID SHUTDOWN REQUIREMENTS MET WHEN INVERTERS AND ALL CONDUCTORS ARE WITHIN ARRAY BOUNDARIES PER NEC 690.12(1).
- CONSTRUCTION FOREMAN TO PLACE CONDUIT RUN PER 690.31(G).
- ARRAY DC CONDUCTORS ARE SIZED FOR DERATED CURRENT.
- 9.66 AMPS MODULE SHORT CIRCUIT CURRENT.
- 15.09 AMPS DERATED SHORT CIRCUIT CURRENT [690.8 (a) & 690.8 (b)].

LEGEND AND ABBREVIATIONS

 SERVICE ENTRANCE	
 MAIN PANEL	 CHIMNEY
 SUB-PANEL	 ATTIC VENT
 PV LOAD CENTER	 FLUSH ATTIC VENT
 SUNRUN METER	 PVC PIPE VENT
 DEDICATED PV METER	 METAL PIPE VENT
 INVERTER(S) WITH INTEGRATED DC DISCONNECT AND AFCI	 T-VENT
 AC DISCONNECT(S)	 SATELLITE DISH
 DC DISCONNECT(S)	 FIRE SETBACKS
 COMBINER BOX	 HARDSCAPE
 INTERIOR EQUIPMENT SHOWN AS DASHED	 - PL - PROPERTY LINE


SCALE: NTS

A	AMPERE
AC	ALTERNATING CURRENT
AFCI	ARC FAULT CIRCUIT INTERRUPTER
AZIM	AZIMUTH
COMP	COMPOSITION
DC	DIRECT CURRENT
(E)	EXISTING
EXT	EXTERIOR
FRM	FRAMING
INT	INTERIOR
LBW	LOAD BEARING WALL
MAG	MAGNETIC
MSP	MAIN SERVICE PANEL
(N)	NEW
NTS	NOT TO SCALE
OC	ON CENTER
PRE-FAB	PRE-FABRICATED
PSF	POUNDS PER SQUARE FOOT
PV	PHOTOVOLTAIC
TL	TRANSFORMERLESS
TYP	TYPICAL
V	VOLTS
W	WATTS



TABLE OF CONTENTS	
PAGE #	DESCRIPTION
PV-1.0	COVER SHEET
PV-2.0	SITE PLAN
PV-3.0	LAYOUT
PV-3.1	LAYOUT
PV-3.2	DETAIL
PV-4.0	ELECTRICAL
PV-5.0	SIGNAGE

VICINITY MAP



Gilbert Correia
GILBERT CORREIA, C10, C46
EC13007964
5208 TAMPA W BLVD, TAMPA, FL 33634
PHONE 0
FAX 0

CUSTOMER RESIDENCE:
RALPH MELOON JR
6609 FRANCONIA DRIVE, BELLE ISLE, FL, 32812

TEL. (907) 252-7110
APN #: 30-23-20-1618-00-030

PROJECT NUMBER:
801R-609MELO

DESIGNER: 720.475.7994
JULIA LONGINOTTI


SHEET
COVER SHEET

REV: A.1 3/12/2018


PAGE PV-1.0

REV	NAME	DATE	COMMENTS

SITE PLAN - SCALE = 1/16" = 1'-0"



	PITCH	TRUE AZIM	MAG AZIM	PV AREA (SQFT)
AR-01	27°	180°	189°	161.8
AR-02	27°	90°	99°	125.8
AR-03	16°	180°	189°	71.9
AR-04	25°	180°	189°	89.9
AR-05	27°	270°	279°	143.8



SUNRUN

EC13007964
 5208 TAMPA W BLVD, TAMPA, FL 33634
 PHONE 0
 FAX 0

CUSTOMER RESIDENCE:
 RALPH MELOON JR
 6609 FRANCONIA DRIVE, BELLE ISLE, FL, 32812

TEL. (907) 252-7110
 APN #: 30-23-20-1618-00-030

PROJECT NUMBER:
 801R-609MELO

DESIGNER: 720.475.7994
 JULIA LONGINOTTI

SHEET
SITE PLAN

REV: A.1 3/12/2018

PAGE
PV-2.0




	ROOF TYPE	MOUNTING DETAIL	ROOF HEIGHT	ROOF EXPOSURE	FRAME MATERIAL	FRAME TYPE	FRAME SIZE	MAX FRAME SPAN	OC SPACING	ROOF EDGE ZONE	MAX RAIL SPAN	MAX RAIL OVERHANG
AR-01	COMP SHINGLE	FLASHED L FOOT. SEE PEN D03.	2 STORY	ATTIC	WOOD	PREFABRICATED TRUSS	2 X 4	8' - 0"	24"	3' - 0"	2' - 0"	2' - 0"
AR-02	COMP SHINGLE	FLASHED L FOOT. SEE PEN D03.	2 STORY	ATTIC	WOOD	PREFABRICATED TRUSS	2 X 4	8' - 0"	24"	3' - 0"	2' - 0"	1' - 4"

DESIGN CRITERIA


MODULES:
 REC SOLAR: REC285TP2 BLK
MODULE DIMS:
 65.94" x 39.25" x 1.49" (38mm)
MODULE CLAMPS:
 Portrait: 8.2" - 16.4"
 Landscape: 4.9" - 9.8"
MAX DISTRIBUTED LOAD: 3 PSF
SNOW LOAD: 0 PSF
WIND SPEED:
 145 MPH 3-SEC GUST.
LAG SCREWS:
 5/16"x3.5": 2.5" MIN EMBEDMENT
NOTE:
 INSTALLERS TO VERIFY RAFTER SIZE, SPACING AND SLOPED SPANS, AND NOTIFY E.O.R. OF ANY DISCREPANCIES BEFORE PROCEEDING.

D1 - AR-01 - SCALE: 3/16" = 1'-0"
 PITCH: 27°
 AZIM: 180°



1
 PV-3.2 ADD (N) 2X6 BLOCKING AS NEEDED FOR PV ATTACHMENT

D2 - AR-02 - SCALE: 3/16" = 1'-0"
 PITCH: 27°
 AZIM: 90°



1
 PV-3.2 ADD (N) 2X6 BLOCKING AS NEEDED FOR PV ATTACHMENT



EC13007964
 5208 TAMPA W BLVD, TAMPA, FL 33634
 PHONE 0
 FAX 0

CUSTOMER RESIDENCE:
 RALPH MELOON JR
 6609 FRANCONIA DRIVE, BELLE ISLE, FL, 32812

TEL. (907) 252-7110
 APN #: 30-23-20-1618-00-030

PROJECT NUMBER:
 801R-609MELO

DESIGNER: 720.475.7994
 JULIA LONGINOTTI

SHEET
 LAYOUT

REV: A.1 3/12/2018


PAGE PV-3.0



ROOF TYPE	MOUNTING DETAIL	ROOF HEIGHT	ROOF EXPOSURE	FRAME MATERIAL	FRAME TYPE	FRAME SIZE	MAX FRAME SPAN	OC SPACING	ROOF EDGE ZONE	MAX RAIL SPAN	MAX RAIL OVERHANG
AR-03 COMP SHINGLE	FLASHED L FOOT. SEE PEN D03.	1 STORY	VAULTED	WOOD	PREFABRICATED TRUSS	2 X 4	8'-0"	24"	3'-0"	2'-0"	2'-0"
AR-04 COMP SHINGLE	FLASHED L FOOT. SEE PEN D03.	1 STORY	ATTIC	WOOD	PREFABRICATED TRUSS	2 X 4	8'-0"	24"	3'-0"	2'-0"	2'-0"
AR-05 COMP SHINGLE	FLASHED L FOOT. SEE PEN D03.	2 STORY	ATTIC	WOOD	PREFABRICATED TRUSS	2 X 4	8'-0"	24"	3'-0"	2'-0"	1'-4"


D3 - AR-03 - SCALE: 3/16" = 1'-0"

PITCH: 16°
AZIM: 180°



D3 - AR-03 - SCALE: 3/16" = 1'-0"

PITCH: 16°
AZIM: 180°



D4 - AR-04 - SCALE: 3/16" = 1'-0"

PITCH: 25°
AZIM: 180°




D4 - AR-04 - SCALE: 3/16" = 1'-0"

PITCH: 25°
AZIM: 180°



D5 - AR-05 - SCALE: 3/16" = 1'-0"

PITCH: 27°
AZIM: 270°




D5 - AR-05 - SCALE: 3/16" = 1'-0"

PITCH: 27°
AZIM: 270°



DESIGN CRITERIA	
MODULES:	REC SOLAR: REC285TP2 BLK
MODULE DIMS:	65.94" x 39.25" x 1.49" (38mm)
MODULE CLAMPS:	Portrait: 8.2" - 16.4"
LANDSCAPE:	4.9" - 9.8"
SNOW LOAD:	0 PSF
WIND SPEED:	145 MPH 3-SEC GUST.
LAG SCREWS:	5/16"x3.5"; 2.5" MIN EMBEDMENT
NOTE:	INSTALLERS TO VERIFY RAFTER SIZE, SPACING AND SLOPED SPANS, AND NOTIFY E.O.R. OF ANY DISCREPANCIES BEFORE PROCEEDING.



EC13007964
5208 TAMPA W BLVD, TAMPA, FL 33634
PHONE 0
FAX 0

CUSTOMER RESIDENCE:
RALPH MELTON JR
6609 FRANCONIA DRIVE, BELLE ISLE, FL, 32812
TEL: (907) 252-7110
APN #: 30-23-20-1618-00-030

PROJECT NUMBER:
801R-609MELO


DESIGNER:
JULIA LONGINOTTI
720.475.7994

SHEET
LAYOUT

REV: A.1
3/12/2018

PAGE
PV-3.1






PV ATTACHMENT BLOCKING

SCALE: NTS

- NOTES:
 1. INSTALLATION CREW TO INSTALL BLOCKING PRIOR TO INSTALLATION OF PV SYSTEM.
 2. CREW TO VERIFY THAT LAG BOLTS HAVE NOT MISSED VERTICAL BLOCKING BEFORE COMPLETION OF JOB.


B

TOP VIEW
SCALE: NTS



A

ELEVATION
SCALE: NTS



EC13007964
 5208 TAMPA W BLVD, TAMPA, FL 33634
 PHONE 0
 FAX 0

CUSTOMER RESIDENCE:
 RALPH MELON JR
 6609 FRANCONIA DRIVE, BELLE
 ISLE, FL, 32812
 TEL: (907) 252-7110
 APN #: 30-23-20-1618-00-030

PROJECT NUMBER:
 801R-609MEL0

DESIGNER:
 JULIA LONGINOTTI
 720.475.7994

SHEET
 DETAIL

REV: A.1 3/12/2018
 PAGE PV-3.2

SUNRUN



ACCEPTABLE MIN. LUMBER TYPE	
LUMBER TYPE	MIN. Fb (psi)
DOUG FIR-LARCH #2	900
SOUTHERN PINE #1	1500
HEM-FIR #2	850
SPRUCE PINE FIR #2	875


SYSTEM CHARACTERISTICS - INVERTER 1
 SYSTEM SIZE: 9405 W
 SYSTEM OPEN CIRCUIT VOLTAGE: 11 V
 SYSTEM OPERATING VOLTAGE: 350 V
 MAX ALLOWABLE DC VOLTAGE: 500 V
 SYSTEM OPERATING CURRENT: 26.87 A
 SYSTEM SHORT CIRCUIT CURRENT: 45 A

MODULE CHARACTERISTICS
 REC SOLAR: REC285TP2 BLK
 OPEN CIRCUIT VOLTAGE: 38.6 V
 MAX INPUT VOLTAGE: 48 VDC
 MIN INPUT VOLTAGE: 8 VDC
P320 OPTIMIZER CHARACTERISTICS:
 285 W
 8 VDC
 38.6 V MAX INPUT VOLTAGE
 48 VDC
 31.9 V MAX INPUT ISC
 11 ADC
 9.66 A MAX OUTPUT CURRENT
 15 ADC

#	CONDUIT	CONDUCTOR	NEUTRAL	GROUND
1	NONE	(6) 10 AWG PV WIRE	NONE	(1) 10 AWG BARE COPPER
2	3/4" EMT OR EQUIV.	(6) 10 AWG THHN/THWN-2	NONE	(1) 10 AWG THHN/THWN-2
3	3/4" EMT OR EQUIV.	(2) 6 AWG THHN/THWN-2	(1) 10 AWG THHN/THWN-2	(1) 8 AWG THHN/THWN-2
4	3/4" EMT OR EQUIV.	(2) 6 AWG THHN/THWN-2	(1) 6 AWG THHN/THWN-2	(1) 8 AWG THHN/THWN-2

CONDUIT SCHEDULE


NOTES TO INSTALLER:
 1. 11 VDC EXPECTED OPEN CIRCUIT STRING VOLTAGE.
 2. CONNECT SYSTEM VIA INSULATION PIERCING ON SUPPLY SIDE OF MAIN BREAKER IN MAIN PANEL ENCLOSURE. CONDUCTORS ARE FIELD INSTALLED.



PAGE PV-4.0
 REV: A.1 3/12/2018
ELECTRICAL
 SHEET
 DESIGNER: JULIA LONGINOTTI
 720.475.7994
 PROJECT NUMBER: 801R-609MELO
 APN #: 30-23-20-1618-00-030
 TEL. (907) 252-7110
 ISLE, FL, 32812
 6609 FRANCONIA DRIVE, BELLE
 RALPH MELON JR
 CUSTOMER RESIDENCE:
 EC13007964
 5208 TAMPA W BLVD, TAMPA, FL 33634
 PHONE 0
 FAX 0



SUNRUN



! WARNING
ELECTRICAL SHOCK HAZARD
 DO NOT TOUCH TERMINALS. TERMINALS ON LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

LABEL LOCATION:
 INVERTER(S), AC DISCONNECT(S), AC COMBINER PANEL (IF APPLICABLE).
 PER CODE(S): CEC 2016: 690.17(E), NEC 2014: 690.17(E), NEC 2011: 690.17(4)

! WARNING
ELECTRICAL SHOCK HAZARD
 IF GROUND FAULT IS INDICATED ALL NORMALLY GROUNDED CONDUCTORS MAY BE UNGROUNDED AND ENERGIZED

LABEL LOCATION:
 INVERTER(S), ENPHASE ENVOY ENCLOSURE (IF APPLICABLE).
 PER CODE(S): CEC 2016: 690.5(C), NEC 2014: 690.5(C), NEC 2011: 690.5(C)

! WARNING
ELECTRICAL SHOCK HAZARD
THE DC CONDUCTORS OF THIS PHOTOVOLTAIC SYSTEM ARE UNGROUNDED AND MAY BE ENERGIZED

LABEL LOCATION:
 INVERTER(S), DC DISCONNECTS.
 PER CODE(S): CEC 2016: 690.35(F), NEC 2014: 690.35(F), NEC 2011: 690.35(F)

! WARNING
DUAL POWER SUPPLY
SOURCES: UTILITY GRID AND PV SOLAR ELECTRIC SYSTEM

LABEL LOCATION:
 UTILITY SERVICE METER AND MAIN SERVICE PANEL.
 PER CODE(S): CEC 2016: 705.12(D)(3), NEC 2014: 705.12(D)(3), NEC 2011: 705.12(D)(4)

! WARNING
INVERTER OUTPUT CONNECTION
DO NOT RELOCATE THIS OVERCURRENT DEVICE

LABEL LOCATION:
 ADJACENT TO PV BREAKER (IF APPLICABLE).
 PER CODE(S): CEC 2016: 705.12(D)(2)(3)(b), NEC 2014: 705.12(D)(2)(3)(b), NEC 2011: 705.12(D)(7)

! WARNING
PHOTOVOLTAIC SYSTEM COMBINER PANEL
DO NOT ADD LOADS

LABEL LOCATION:
 PHOTOVOLTAIC AC COMBINER (IF APPLICABLE).
 PER CODE(S): CEC 2016: 705.12(D)(2)(3)(c), NEC 2014: 705.12(D)(2)(3)(c), NEC 2011: 705.12(D)(4)

WARNING: PHOTOVOLTAIC POWER SOURCE

LABEL LOCATION:
 INTERIOR AND EXTERIOR DC CONDUIT EVERY 10 FT, AT EACH TURN, ABOVE AND BELOW PENETRATIONS, ON EVERY JB/PULL BOX CONTAINING DC CIRCUITS.
 PER CODE(S): CEC 2016: 690.31(G)(3), 690.31(G)(4), NEC 2014: 690.31(G)(3), 690.31(G)(4), NEC 2011: 690.31(E)(3), 690.31(E)(4), IFC 2012: 605.11.1.4

PHOTOVOLTAIC AC DISCONNECT
 MAXIMUM AC OPERATING CURRENT: 41.67 AMPS
 NOMINAL OPERATING AC VOLTAGE: 240 VAC

LABEL LOCATION:
 AC DISCONNECT(S), PHOTOVOLTAIC SYSTEM POINT OF INTERCONNECTION.
 PER CODE(S): CEC 2016: 690.54, NEC 2014: 690.54, NEC 2011: 690.54

INVERTER 1

PHOTOVOLTAIC DC DISCONNECT		
RATED MAXIMUM POWER-POINT CURRENT:	26.87	ADC
RATED MAXIMUM POWER-POINT VOLTAGE:	350	VDC
MAXIMUM SYSTEM VOLTAGE:	500	VDC
MAXIMUM SHORT CIRCUIT CURRENT:	45	ADC

LABEL LOCATION:
 INVERTER(S), DC DISCONNECT(S).
 PER CODE(S): CEC 2016: 690.53, NEC 2017: 690.53, NEC 2014: 690.53, NEC 2011: 690.53

PHOTOVOLTAIC SYSTEM EQUIPPED WITH RAPID SHUTDOWN

LABEL LOCATION:
 UTILITY SERVICE ENTRANCE/METER, INVERTER/DC DISCONNECT IF REQUIRED BY LOCAL AHJ, OR OTHER LOCATIONS AS REQUIRED BY LOCAL AHJ.
 PER CODE(S): CEC 2016: 690.12, NEC 2014: 690.12, NEC 690.56, IFC 2012: 605.11.1

NOTES AND SPECIFICATIONS:


- SIGNS AND LABELS SHALL MEET THE REQUIREMENTS OF THE NEC 2014 ARTICLE 110.21(B), UNLESS SPECIFIC INSTRUCTIONS ARE REQUIRED BY SECTION 690, OR IF REQUESTED BY THE LOCAL AHJ.
- SIGNS AND LABELS SHALL ADEQUATELY WARN OF HAZARDS USING EFFECTIVE WORDS, COLORS AND SYMBOLS.
- LABELS SHALL BE PERMANENTLY AFFIXED TO THE EQUIPMENT OR WIRING METHOD AND SHALL NOT BE HAND WRITTEN.
- LABEL SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED.
- SIGNS AND LABELS SHALL COMPLY WITH ANSI Z535.4-2011, PRODUCT SAFETY SIGNS AND LABELS, UNLESS OTHERWISE SPECIFIED.
- DO NOT COVER EXISTING MANUFACTURER LABELS.



SUNRUN	
EC13007964	
5208 TAMPA W BLVD. TAMPA, FL 33634 PHONE 0 FAX 0	
CUSTOMER RESIDENCE: RALPH MELOON JR 6609 FRANCONIA DRIVE, BELLE ISLE, FL, 32812	
TEL. (907) 252-7110 APN #: 30-23-20-1618-00-030	
PROJECT NUMBER: 801R-609MELO	
DESIGNER:	720.475.7994
JULIA LONGINOTTI	
SHEET	SIGNAGE
REV: A.1	3/12/2018
PAGE	PV-5.0



REC TWINPEAK 2 SERIES



Measurements in mm (in)

ELECTRICAL DATA @ STC	Product Code*: RECxxxTP2				
Nominal Power - P_{MPP} (Wp)	275	280	285	290	295
Watt Class Sorting - (W)	0/+5	0/+5	0/+5	0/+5	0/+5
Nominal Power Voltage - V_{MPP} (V)	31.5	31.7	31.9	32.1	32.3
Nominal Power Current - I_{MPP} (A)	8.74	8.84	8.95	9.05	9.14
Open Circuit Voltage - V_{OC} (V)	38.2	38.4	38.6	38.8	39.0
Short Circuit Current - I_{SC} (A)	9.52	9.61	9.66	9.71	9.76
Panel Efficiency (%)	16.5	16.8	17.1	17.4	17.7

Values at standard test conditions STC (air mass AM 1.5, irradiance 1000 W/m², cell temperature 25°C).
At low irradiance of 200 W/m² (AM 1.5 and cell temperature 25°C) at least 95% of the STC module efficiency will be achieved.
*Where xxx indicates the nominal power class (P_{MPP}) at STC above, and can be followed by the suffix BLK for black framed modules.

ELECTRICAL DATA @ NOCT	Product Code*: RECxxxTP2				
Nominal Power - P_{MPP} (Wp)	206	210	214	218	223
Nominal Power Voltage - V_{MPP} (V)	29.2	29.4	29.6	29.8	30.0
Nominal Power Current - I_{MPP} (A)	7.07	7.15	7.24	7.32	7.43
Open Circuit Voltage - V_{OC} (V)	35.4	35.6	35.8	36.0	36.2
Short Circuit Current - I_{SC} (A)	7.52	7.59	7.68	7.75	7.85

Nominal operating cell temperature NOCT (800 W/m², AM 1.5, wind speed 1 m/s, ambient temperature 20°C).
*Where xxx indicates the nominal power class (P_{MPP}) at STC above, and can be followed by the suffix BLK for black framed modules.

CERTIFICATIONS



UL 1703, Fire classification Type 2, IEC 61215, IEC 61730,
IEC 61701 (Salt Mist - severity level 6), IEC 62804 (PID Free),
IEC 62716 (Ammonia Resistance), ISO 11925-2 (Ignitability Class I),
UN1845/79174 (Class A), ISO 9001:2015, ISO 14001:2015, ISO 45001:2018

WARRANTY

10 year product warranty
25 year linear power output warranty
(max. degradation in performance of 0.7% p.a. from 97% after the first year)
See warranty conditions for further details.

17.7% EFFICIENCY
10 YEAR PRODUCT WARRANTY
25 YEAR LINEAR POWER OUTPUT WARRANTY

DUTY*FREE US IMPORT DUTY FREE

TEMPERATURE RATINGS

Nominal operating cell temperature (NOCT)	44.6°C (±2°C)
Temperature coefficient of P_{MPP}	-0.36%/°C
Temperature coefficient of V_{OC}	-0.30%/°C
Temperature coefficient of I_{SC}	0.066%/°C

GENERAL DATA

Cell type:	6 strings of 20 REC HC multicrystalline PERC
Glass:	0.13" (3.2 mm) solar glass with anti-reflective surface treatment
Back sheet:	Highly resistant polyester polyolefin construction
Frame:	Anodized aluminum (available in silver or black)
Junction box:	IP67 rated, 3-part with 3 bypass diodes 12 AWG (4 mm ²) PV wire 35" x 47" (0.9 m x 1.2 m)
Connectors:	Stäubli MC4 PV-KBT4/PV-KST4, 12 AWG (4 mm ²)
Origins:	Silicon: Made in USA & Norway Wafer/Cell/Module: Made in Singapore

MAXIMUM RATINGS

Operational temperature:	-40 ... +185°F (-40 ... +85°C)
Maximum system voltage:	1000 V
Design Loads:	(+) 75.2 lbs/ft ² (3600 Pa) (-) 33.4 lbs/ft ² (1600 Pa) Refer to installation manual
Max series fuse rating:	20 A
Max reverse current:	20 A

MECHANICAL DATA

Dimensions:	65.9 x 39.25 x 1.5 (1675 x 997 x 38 mm)
Area:	1798 ft ² (167 m ²)
Weight:	40.8 lbs (18.5 kg)

Note! Specifications subject to change without notice




www.recgroup.com

Materials Included In Series 100 Standoff Kit (Steel Structural Member):

- ① (1) SnapNrack Standoff Base
- ② (1) SnapNrack Standoff Shaft
- ③ (1) SnapNrack Rubber Rain Collar
- ④ (1) SnapNrack Standoff Clamp
- ⑤ (1) 5/16in SS Split Lock Washer
- ⑥ (1) 5/16in - 18 X 2in SS HCS Bolt
- ⑦ (1) SnapNrack Bonding Channel Nut, 5/16in - 18



Standard Standoff Base



Other Materials Required:

- ① (1) 1/4in Tek Screw
- ① (1) Roof Cone Flashing

When To Use:
Steel Structural
Member Configurations



Materials Included In Series 100 Four Hole Standoff Kit:

- ① (1) SnapNrack Four Hole Standoff Base
- ② (1) SnapNrack Standoff Shaft
- ③ (1) SnapNrack Rubber Rain Collar
- ④ (1) SnapNrack Standoff Clamp
- ⑤ (1) 5/16in SS Split Lock Washer
- ⑥ (1) 5/16in - 18 X 2in SS HCS Bolt
- ⑦ (1) SnapNrack Bonding Channel Nut, 5/16in - 18



Four Hole Base



Other Materials Required:

- ① (4) Wood Screws 1/4"
- ② (1) Roof Cone Flashing

When To Use:
TJI Jolsts




Series 100 UL Standoff Post

Required Tools:

Hammer or Stud Finder
 Roof Marking Crayon
 Drill with 1/8 inch Pilot Drill Bit
 Roof Sealant
 Torque Driver with Bit Adapter
 Channel Locks
 1/2 inch Socket Wrench

When To Use:
 Concrete or Clay Tile Roofs



Materials Included In Series 100 Standoff Kit:

- ① (1) SnapNrack Standoff Base
- ② (1) SnapNrack Standoff Shaft
- ③ (1) SnapNrack Rubber Rain Collar
- ④ (1) SnapNrack Standoff Clamp
- ⑤ (1) 5/16in SS Split Lock Washer
- ⑥ (1) 5/16in - 18 X 2in SS HCS Bolt
- ⑦ (1) SnapNrack Bonding Channel Nut, 5/16in - 18

Other Materials Required:


- ① (1) 5/16in Lag Screw
- ② (1) 5/16in Washer
- (1) Roof Cone Flashing

Technical Standoff Shaft Data:


Material	6000 Series Heat Treated Aluminum
Finish	Mill
Weight	5.5" Shaft = 0.4 LBS 7" Shaft = 0.5 LBS 8.5" Shaft = 0.6 LBS
Design Uplift Load	200 LBS Uplift
Design Ultimate Load	1600 LBS Uplift

All Standoff shafts
 are mill finished

Dimensioned Assembly



Dimensioned Shaft




Required Tools:

Hammer Or Stud Finder
 Roof Marking Crayon
 Drill with 1/8 inch Pilot Drill Bit
 Roof Sealant
 Torque Driver with Bit Adapter
 1/2 inch Socket Wrench

Materials Included in Series 100 L-Foot Kit:


- ① (1) SnapNrack Flashed Base
- ② (1) SnapNrack Composition Flashing
- ③ (1) SnapNrack L Foot, Composition 92°
- ④ (1) 5/16in- 18 SS Flange Hex Nut
- ⑤ (1) 5/16in Flange Bolt
- ⑥ (1) SnapNrack Bonding Channel Nut, 5/16in - 18

Dimensioned L-Foot



Other Materials Required:

- ① (1) 5/16 in Lag Screw
- ② (1) 5/16 in Washer




When To Use:
 Composite Shingle Roofs

Technical L-Foot Data:


Material	6000 Series Heat Treated Aluminum
Finish	Class 2 Anodized Finish Clear and Black Finish Available
Weight	0.16 LBS
Design Uplift Load	200 LBS Uplift
Design Ultimate Load	1000 LBS Uplift

Dimensioned Assembly



Survey the Site


- Measure the roof surfaces and develop an accurate drawing, including any obstacles such as chimneys and roof vents.
- If plans are available, check to make sure that the plans match the final structure.
- Review the shading pattern across the roof surface from the residence itself, from adjacent structures, and from other nearby features such as trees.
- Identify any roof access areas or keep-out areas as required by the local jurisdiction.
- Confirm roof construction, type, and condition.
- Assess roof rafter size, material, and spacing to confirm that the structure is sound and can support the additional load of the array.
- Identify any construction anomalies that may complicate the process of locating rafters from the roof surface.
- If you find structural problems such as termite damage or cracked rafters that may compromise the structure's integrity, consult a structural engineer.



Develop a Layout

Using the information collected in the site survey and from the span tables, complete a system layout showing array location and distances from key roof features. Include any information necessary for the permitting process.

Typically, PV modules are installed in portrait mode, with the long side of the module running up the roof slope and the rails running horizontally across the roof perpendicular to the roof rafters, which commonly run down slope.



Series 100 UL Introduction

SnapNrack Series 100 UL PV Mounting System offers a low profile, visually appealing, photovoltaic (PV) module installation system. This innovative system simplifies the process of installing solar PV modules, shortens installation times, and lowers installation costs.

SnapNrack systems, when installed in accordance with this manual, will be structurally adequate for the specific installation site and will meet the local and International Building Code. Systems will also be bonded to ground, under SnapNrack's UL 2703 Certification.

The SnapNrack installation system is a set of engineered components that can be assembled into a wide variety of PV mounting structures. It is designed to be installed by qualified solar installation technicians. With SnapNrack you will be able to solve virtually any PV module mounting challenge.

Table of Contents


Step 1: Project Plans	
Configuration	3
Surveying and Layout.	4
Step 2: Roof Attachment	
Flashed L-Foot- For Composition Shingle	6
Standoff Post- For All Roofing Types	8
Standoff Options	10
Universal Tile Roof Hook	12
Flat Tile Roof Hook.	14
Hanger Bolt- For All Roofing Types	16
Metal Roof Base	18
Corrugated Roof Block- For Corrugated Metal	20
Tilt Mount 5°-15°	22
Tilt Mount 10°-45°	24
Seam Clamp- For Standing Metal Seam	26
Step 3: Leveling Rails	
installing and Leveling Rails	28
Step 4: Attaching Modules	
Attaching Modules	30
Step 5: Select Any Racking Accessories	
Edge Screen	32
Wire Management.	34
Micro inverter Attachment.	36
Rail Cutting Tool and End Cap	40
System Ground	
System Ground	38
High Tilt Tool	
High Tilt Tool.	42
Appendix	44



SolarEdge Single Phase StorEdge Inverter for North America SE7600A-US

	Lower Power Output	Higher Power Output	
STANDARD COMPLIANCE			
Safety	UL1741, UL1741 SA, UL1699B, UL1998, CSA 22.2		
Grid Connection Standards	IEEE1547, Rule 21, Rule 14H		
Emissions	FCC part15 class B		
INSTALLATION SPECIFICATIONS			
AC Output (Loads/Grid) conduit size / AWG range	1" / 14-6 AWG		
AC Output (Backup) conduit size / AWG range	0.75-1" knockouts / 14-6 AWG		
AC Input (Auto-transformer) conduit size / AWG range	0.75-1" / 14-6 AWG		
DC Input (PV) conduit size / AWG range	0.75" / 14-8 AWG		
DC Input (Battery) conduit size / AWG range	0.75" / 12-10 AWG		
Dimensions with Connection Unit (HxWxD)	37 x 12.5 x 7.2 / 940 x 315 x 184		in / mm
Weight with Connection Unit	58.5 / 26.5		lb / kg
Cooling	Natural convection and internal fan (user replaceable)		
Noise	<50		dB(A)
Min - Max Operating Temperature	-13 to +140 / -25 to +60		°F / °C
Protection Rating	NEMA 3R		

Inverter Interface






SolarEdge Single Phase StorEdge™ Solutions for North America

StorEdge™ Features:

- Smart Energy Management - export control, time-of-use shifting, maximized self-consumption, demand response and peak shaving capabilities
- Backup power - automatically provides power to backed-up loads in the event of grid interruption
- All-in-one solution uses a single DC optimized phase inverter to manage and monitor both PV generation and energy storage
- Compatible with the LG Chem RESU battery.



SolarEdge StorEdge™ Solutions for North America - Product Selector

	Grid-tied solar, backup power and smart energy management	Grid-tied solar and backup power	Grid-tied solar and smart energy management
Single Phase StorEdge™ Inverter	✓	✓	✓
Auto-transformer	✓	✓	
SolarEdge Electricity Meter	✓		✓
Battery	✓	✓	✓